
ER-RB · ROCKBLOCK CAMPUS MODULE

CAMPUS ISOMETRIC, 250 MW



EQUIPMENT KEY

1. Genset unit, 500 kW (G-nnn-k)
2. GCB, generator collector box, 480 V (GCB-nnn)
3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)
5. 35 kV switchgear lineup e-house (SWG-x)
6. Data center, customer (ghosted)
7. Ownership line: ER scope / customer scope, TO VERIFY
8. Operations / maintenance building
9. Warehouse
10. Water retention
11. Gas metering skid
13. Access road

NOTES

100 RockBlocks, 500 units of 500 kW, 13 groups of 8 on 35 kV loops, 4 switchgear lineups along the fence nearest the data center.

Isometric drawing: lengths along the three isometric axes are true at 1:4,800; the graphic bar lies on the X axis. Base view: no circuits drawn (they live in the cable layers and SK-2305).

The data center is ghosted beyond the ownership line; its size is not modelled.

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2301

ER-RB REV 00
Oct 26, 2026

SCALE 1:4,800 along the isometric axes


Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up


Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION

PLAN



ELEVATION, LOOKING NORTH



1:180 (1 in = 15 ft)

0 5 10 20 30 ft

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION · Stephan Hardt - Power Generation Solutions · ER-RB Rev 00 SK-2302

ER-RB · ROCKBLOCK CAMPUS MODULE

BLOCK PLAN AND ELEVATION, RB-NNN

EQUIPMENT KEY

1. Genset unit, 500 kW (G-nnn-k)
2. GCB, generator collector box, 480 V (GCB-nnn)
3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)
4. 35 kV loop corridor
13. Access road

NOTES

One RockBlock in local coordinates, road side north. Dimension strings carry their status: K known, WA working assumption, TV to verify.

Unit footprint 10 x 8 ft KNOWN (ERT500 release); 448 sq ft per 2.5 MW block KNOWN (erock.com); unit height, GCB and transformer sizes are placeholders TO VERIFY.

Stack top EL 25: TCEQ gas-EGU standard permit minimum, working assumption.

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2302

ER-RB REV 00
Oct 26, 2026

SCALE 1:180 (plan and elevation)


Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up


Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION

PLAN RB-001 WITH ITS CIRCUITS



ONE-LINE, ONE BLOCK (NOT TO SCALE)



1:180 plan (1 in = 15 ft)

ft

0 5 10 20

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION · Stephan Hardt - Power Generation Solutions · ER-RB Rev 00 SK-2303

ER-RB · ROCKBLOCK CAMPUS MODULE

ONE BLOCK ELECTRICAL: L1, L2, GCB, TRANSFORMER

EQUIPMENT KEY

1. Genset unit, 500 kW (G-nnn-k)
2. GCB, generator collector box, 480 V (GCB-nnn)
3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)
4. 35 kV loop corridor

NOTES

L1 480 V generator leads, KNOWN topology: unit terminal box to its own GCB breaker; 2 parallel sets of 4 x 1/C per unit (count and size TO VERIFY).

L2 block feed GCB to transformer LV: 8 parallel sets of 4 x 1/C or bus duct, TO VERIFY.

L6 ground ring 4/0 bare Cu with taps, L7 control + Cat6A per unit: working assumptions.

Circuits drawn at trench depth (EL -3); risers into the equipment bottoms.

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2303

ER-RB REV 00

Oct 26, 2026

SCALE 1:180 (plan); one-line not to scale

Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up


Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION

ER-RB · ROCKBLOCK CAMPUS MODULE

35 KV LOOP AND LINEUP TOPOLOGY

ONE-LINE, 250 MW CAMPUS (NOT TO SCALE)



o block transformer XFMR-nnn on the loop [] breaker L3 amber loop, L4 dashed ties, L5 red feeders to data center (L5, TV)


BREAKER COUNT RECONCILED

Group breakers (one per loop)	13
Tie breakers (2 per lineup, ring)	8
Feeder breakers (one per lineup)	4
Spare sections (one per lineup)	4
Breakers + spares, total	29
Loops = groups	13
Transformers on loops = blocks	100

Check: 13 x 1 + 4 x (2 ties + 1 feeder + 1 spare) = 29

100 blocks / 8 per loop = 12.5 -> 13 loops

KEY PLAN



EQUIPMENT KEY

3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)
4. 35 kV loop corridor
5. 35 kV switchgear lineup e-house (SWG-x)
6. Data center, customer (ghosted)
7. Ownership line: ER scope / customer scope, TO VERIFY

NOTES

One loop per group: out from the group breaker, through every block transformer, home to the same lineup (loop return position TO VERIFY: same breaker or a second one).

Lineup ties close a ring A-B-...-A (KNOWN: switchgear-to-switchgear loops for redundancy).

One ~75 MW feeder per lineup to the data center; scope owner TO VERIFY.

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2304

ER-RB REV 00

Oct 26, 2026

SCALE one-line NTS; key plan 1:9,600


Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up

Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION · Stephan Hardt - Power Generation Solutions · ER-RB Rev 00 SK-2304

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION



L1 480 V generator leads · L2 480 V block feed · L3 35 kV collector loop · L4 35 kV lineup ties
L5 ~75 MW feeders to the data center · L6 Grounding · L7 Control / comms

1:2,880 (1 in = 240 ft)

0 100 200 400 ft

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION · Stephan Hardt - Power Generation Solutions · ER-RB Rev 00 SK-2305

ER-RB · ROCKBLOCK CAMPUS MODULE

FOUR-VIEW X-RAY: CONTEXT, SOURCES, DISTRIBUTION, REACH

EQUIPMENT KEY

1. Genset unit, 500 kW (G-nnn-k)
3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)
5. 35 kV switchgear lineup e-house (SWG-x)
6. Data center, customer (ghosted)
7. Ownership line: ER scope / customer scope, TO VERIFY

NOTES

The same two lineup bands (SWG-A and SWG-B, eight groups) four times, adding cable layers: 1 context, 2 sources (L1 / L2 at every block), 3 internal distribution (L3 loops, L6, L7), 4 plant-wide reach (L4 ties, L5 feeders across the ownership line).

Base views stay clean; these are the cable layers, drawn at trench depth.

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2305

ER-RB REV 00
Oct 26, 2026

SCALE 1:2,880 (all four views)

Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up

Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION

PER-BLOCK CABLE KIT · RB-001 (EVERY BLOCK IS THE SAME)

LAYER	CIRCUIT	FROM - TO	RUNS	COND	LEN/RUN FT	CUT FT	COND-FT	CONSTRUCTION
L1	L1-001-1	G-001-1 → GCB-001	2	4	54.1	64.5	516	600 V 1/C XHHW-2 / TC-ER, Cu/Al, size TV
L1	L1-001-2	G-001-2 → GCB-001	2	4	47.2	57.1	457	600 V 1/C XHHW-2 / TC-ER, Cu/Al, size TV
L1	L1-001-3	G-001-3 → GCB-001	2	4	40.3	49.6	397	600 V 1/C XHHW-2 / TC-ER, Cu/Al, size TV
L1	L1-001-4	G-001-4 → GCB-001	2	4	33.5	42.3	338	600 V 1/C XHHW-2 / TC-ER, Cu/Al, size TV
L1	L1-001-5	G-001-5 → GCB-001	2	4	26.7	34.9	279	600 V 1/C XHHW-2 / TC-ER, Cu/Al, size TV
L2	L2-001	GCB-001 → XFMR-001	8	4	12.1	19.2	613	600 V 1/C XHHW-2 (or bus duct, TV)
L6	L6-001	RB-001 grid → ring	1	1	199.0	215.2	215	4/0 bare Cu, ground ring
L6	L6-001-T1..T8	ring → 8 taps	1	1	59.8	64.1	62	2/0 bare Cu, tap
L7	L7-001-1	G-001-1 → GCB-001	2	1	59.3	70.1	140	12/C #14 TC-ER control + Cat6A, per unit
L7	L7-001-2	G-001-2 → GCB-001	2	1	52.4	62.6	125	12/C #14 TC-ER control + Cat6A, per unit
L7	L7-001-3	G-001-3 → GCB-001	2	1	45.6	55.3	111	12/C #14 TC-ER control + Cat6A, per unit
L7	L7-001-4	G-001-4 → GCB-001	2	1	38.7	47.8	96	12/C #14 TC-ER control + Cat6A, per unit
L7	L7-001-5	G-001-5 → GCB-001	2	1	31.9	40.5	81	12/C #14 TC-ER control + Cat6A, per unit

Block kit total, MEASURED: 3,430 conductor-ft

CAMPUS ROLL-UP · CONDUCTOR-FT BY LAYER · SAME MODEL, THREE CAMPUSES

LAYER	FAMILY	STATUS	BASIS	250 MW	500 MW	1,000 MW
L1	480 V generator leads	K	MEASURED	198,605	397,393	794,993
L7	Control / comms	WA	MEASURED	75,526	150,308	301,377
L2	480 V block feed (GCB to transformer)	TV	MEASURED	61,300	122,600	245,200
L6	Grounding	WA	MEASURED	28,532	56,856	113,504
L3	35 kV collector loop (the quoted scope)	K	MEASURED	64,718	127,183	256,644
L4	35 kV lineup ties	K	MEASURED	19,187	38,472	77,042
L5	~75 MW feeders to the data center	TV	ASSUMED	57,152	100,016	185,744
Total, MEASURED rows				447,868	892,812	1,788,760
Total, ASSUMED rows (never added to the measured total)				57,152	100,016	185,744
				100 blk · 13 grp · 4 SWG	200 blk · 25 grp · 7 SWG	400 blk · 50 grp · 13 SWG

VERIFICATION REGISTER · OPEN ITEMS (TO VERIFY) AND WHERE TO CHECK

TV	Distribution / collection voltage (34.5 kV vs 13.8 kV): 34.5 kV	Cliff / ER engineering
TV	480 V generator leads: parallel sets per generator: 2 parallel sets	Cliff / ER engineering
TV	480 V lead size and construction: 4 x 1/C 500 kcmil (3 phase + EGC), 600 V	Cliff / ER engineering
TV	GCB to transformer LV: parallel sets (or bus duct): 8 parallel sets	Cliff / ER engineering
TV	Block feed construction, cable vs bus: 4 x 1/C 600 kcmil (3 phase + N), 600 V	Cliff / ER engineering
TV	~75 MW feeder: parallel 35 kV sets per lineup: 3 parallel sets	Cliff / ER engineering
TV	Whether the ~75 MW feeders are in ER scope: customer or ER	Cliff (one line)
TV	ERT500 enclosure: 10 x 8 ft footprint KNOWN: 9 ft height TO VERIFY: 10 x 8 x 9 ft	ERT500 spec sheet (erock.com/ert500-spec
TV	GCB (480 V panelboard, 5 breakers) L x W x H (placeholder): 10 x 4 x 7.5 ft	ER product sheet
TV	3 MVA pad-mount L x W x H (placeholder): 9 x 9 x 7 ft	ER / transformer data sheet
TV	35 kV switchgear e-house L x W x H (placeholder): 64 x 16 x 14 ft	ER / switchgear data sheet

ER-RB · ROCKBLOCK CAMPUS MODULE

PER-BLOCK TAKEOFF, CAMPUS ROLL-UP, VERIFICATION REGISTER

EQUIPMENT KEY

1. Genset unit, 500 kW (G-nnn-k)
2. GCB, generator collector box, 480 V (GCB-nnn)
3. Step-up transformer, 480 V : 34.5 kV (XFMR-nnn)

NOTES

cut = (routed + risers + terminations + slack) x (1 + spare); conductor-ft = cut x conductors x runs.

MEASURED off the model's routes; ASSUMED = a stated typical length per run. The two totals are never summed. L5 feeders on the ASSUMED basis until their scope is confirmed.

No stock numbers, no dollars. CSV / JSON carry every circuit.



key plan 1:480

0 20 40 ft

STATUS

KNOWN | WORKING ASSUMPTION | TO VERIFY

SK-2306

ER-RB REV 00
Oct 26, 2026

SCALE key plan 1:480; tables n/a

Stephan Hardt - Power Generation Solutions

Letter landscape · 300 dpi · true feet · X east, Y north, EL up

Sources: Oct 26, 2026 call; public record (ERock S-1/A, 10-Q Q2 2026, ERT500 release, PUCT Docket 59076). Nothing under NDA.

CONCEPTUAL ILLUSTRATION · NOT ENGINEERED · NOT FOR CONSTRUCTION